

Sun Petrochemicals Private Limited

1004, 10th Floor, ATL Corporate Park, Saki Vihar Road,
Powai, Mumbai - 400 072, Maharashtra, BHARAT.
CIN: U24219MH1995PTC46424
Tel: +91 22 69325300, + 91 22 28470484
Website: www.sunpetro.com;



No. SunPetro/Bhaskar/Storage Tank/2025-26/SPPL-234/Bulletin-2

Date:09.04.2026

BULLETIN #2

Sub: Crude Oil Storage Tanks at Bhaskar-I Field, Gujarat.

Ref: Tender No.: SunPetro/Bhaskar/Storage Tank/2025-26/SPPL-234

Sun Petrochemicals Private Limited (SunPetro), hereby authorized following amendment / clarification in the above referred Tender:

Sr No	Tender Section	Page No	Clause / Reference	Query Topic	Bidder Queries	SunPetro Response
1	Section III – SOW	Page 27	Clause 3.2	Construction Water	As per our understanding, hydrotest water shall be provided by the Client. Kindly clarify the scope and responsibility for construction water required for civil works, construction activities.	Bidder understanding is correct regarding hydrotest water. Construction water shall be in the scope of the Contractor. as per tender condition responsibility matrix, Pg. 48, Clause 3.5
2	Section III – SOW	Page 26	Clause 3.1(g)	Civil Work	Kindly provide the soil investigation report and foundation design/drawings or clarify whether the same shall be carried out by the Contractor post-award.	Bidder to design foundation as per tender condition, responsibility matrix, Pg. 48, Clause 1.1 and SOW page 26, Clause 3.1(g). Soil investigation report enclosed.
3	Section III – SOW	Page 26	Clause 3.1	Prefabrication vs Erection Distance	Kindly confirm the approximate distance between the prefabrication / material storage yard and the tank erection area, along with availability of suitable internal access roads.	It will be within the CPF premises and will be decided during site visit after the award of contract.
4	Section III – SOW	Page 26	Clause 3.1	PESO Approval	As per our understanding, PESO approval is within the Contractor's scope. Kindly confirm the same and also clarify responsibility for statutory fees and applicability of time extension due to authority-related delays.	Company confirms timely PESO approval is in contractors' scope (refer Page: 48 Clause 3.1).
5	Section III – SOW	Page 27	Clause 3.2	Space for Storage & Fabrication	As per our understanding, space for site storage of materials and machine work shall be in the Client's scope , provided	Company confirms bidder's understanding

					free of cost. Kindly confirm the same.	
6	Section V – QA/QC	Pages 40–46	QA Plan	Third-Party Inspection (TPI)	Kindly clarify whether the Third-Party Inspection (TPI) agency shall be appointed by the Owner or by the Contractor and indicate the responsibility for associated costs.	Company clarifies that TPI agency shall be appointed by the Owner. (Page 48, Clause 4.1).
7	Section III – SOW	Page 62	BOQ	Firefighting System	Kindly provide the line sizes and basic piping details to enable accurate assessment or Clarify whether the same shall be carried out by the contractor.	Design and Engg. is in the scope of the bidder which will be duly approved by company.
8	Section VII – BOQ	Page 62	BOQ	Instrumentation & Electrical Scope	As per BOQ and tender documents, we understand that Instrumentation and Electrical works are not included in the Contractor's scope. Kindly confirm this understanding.	Bidders understanding is not correct. Electrical and Instrumentation will be in contractor's scope as per bid requirement. (Refer SoW and Responsibility matrix.)
9	Section III – SOW	Pages 25–31	General	Greenfield Scope	Kindly confirm that no brownfield tie-ins, shutdown activities, or work within live operating facilities are envisaged under the scope of this tender	Bidders understanding is not correct. Few brownfield tie-ins, shutdown activities, or work within live operating facilities are envisaged under the scope of this tender.
10	Section III – SOW	Pages 25–31	General	Plot Plan / Layout	Kindly provide a plot plan / general layout,	Tentative plot plan is attached
11	Section VII – BOQ	Page 62	General	Cathodic protection	As per our understanding, Cathodic Protection is within the Client's scope. Kindly confirm this understanding	Bidder's understanding is not correct. Cathodic protection is on the scope of the contractor. Please refer Sow, Responsibility Matrix S. No -7 and Price Schedule
12			General	Area Barricading	Please provide Area Barricading Details	It will be firm up during detail engineering by the successful bidder.
13			General		The tender specifies applicable design codes; however, site-specific design parameters such as seismic zone, design wind speed, ambient	1. Elevation above Sea Level: 15.24 m above sea level 2. Ambient temperature (min./max.): 8 / 45 °C 3. Relative Humidity:60%

				temperature, and other governing environmental conditions are not explicitly stated. Kindly please provide the general details for design	4. Average Annual Rainfall: 800–900 mm 5. Basic Wind Speed: 44 m/s 6. Seismic Consideration: As per IS 1893
--	--	--	--	--	---

All other terms and conditions of the Tender remain unchanged.

Regards,

Sun Petrochemicals Pvt. Ltd