

Sun Petrochemicals Private Limited

8th,9th & 10th Floor, ATL Corporate Park, Saki Vihar Road,
Powai, Mumbai - 400 072, Maharashtra, BHARAT.
CIN: U24219MH1995PTC464242
Tel: +91 22 69325300, + 91 22 28470484
Website: www.sunpetro.com;



No. SunPetro/Gujarat/Logging/2026-27/SPPL-297/Bulletin-1

Date:25.06.2026

BULLETIN #1

Sub: Hiring of Logging & Perforation Services for Gujarat Fields.

Ref: Tender No. SunPetro/Gujarat/Logging/2026-27/SPPL-297

Sun Petrochemicals Private Limited (SunPetro), hereby authorized following amendment / clarification in the above referred Tender:

S. No.	Section No, Page No. and Clause No.	Description of Clarification	SunPetro Response
1	Page 79/ BILL OF QUANTITY (BOQ) / PRICE SCHEDULE (PS)	Most likely or evaluation quantities for the required services are not available. Bidder requests the company to provide the most likely quantities for each service	The quantities indicated in the Tender are for bid evaluation purposes only and do not represent the actual quantities to be executed under the Contract. Tentative quantities for various services have been provided in the revised Price Schedule enclosed as Addendum-1 for the purpose of submission and evaluation of bids. Actual quantities shall depend upon the operational requirements during the Contract Period.

All other terms and conditions of the Tender remain unchanged.

Regards,

Sun Petrochemicals Pvt. Ltd.

The bidder shall quote as per the following format.

Sr No.	Description of service	UOM	Est Qty	Unit Price (INR/USD)
1	Day Rate For Logging Unit including Crew	Per Day	100	
2	Standby Rate For Logging Unit including Crew	Per Day	15	
3	Gamma Ray	Per Run	90	
	High Resolution Lateral Log	Per Run	40	
	Micro Spherically Focused Log (MSFL)	Per Run	40	
	Compact Combo Tool having Res, Compensated Neutron, Compensated Density, GR, & Cal	Per Run	40	
	Power or Mechanical Six arm caliper	Per Run	40	
	Cement Bond Evaluation Log	Per Run	40	
	Cement Channel Analyser	Per Run	40	
	Formation Tester with Sampler and GR (25 pretests and 3 samples per run)	Per Run	10	
	Dual packer Module of Formation tester	Per Run	5	
	Insitu Fluid Analyser Module of Formation Tester	Per Run	5	
	Gamma Ray Spectrometry-GR	Per Run	10	
	Dipole Sonic	Per Run	40	
	Full Bore Resistivity Imager	Per Run	15	
	3D Resistivity	Per Run	15	
	Elemental Capture Spectroscopy Log-GR	Per Run	15	
	Nuclear magnetic Resonance Log	Per Run	15	
	Cased hole Reservoir saturation Log	Per Run	15	
	PLT-GR (Full bore flowmeter, Quartz pressure gauge, Temperature and density)	Per Run	10	
	Side Wall Core-GR (24 cores per run)	Per Run	15	
	Free Point Indicator	Per Run	10	
	Bridge Plug & Cement Retainer Setting Tool (PST-CCL & JB-CCL)	Per Run	10	
	Radial cutting Torch	Per Run	5	
	Motorized coring tool	Per Run	10	
Pipe Conveyed Logging (PCL)	Per Job	10		
4	Using 3 3/8" HSC guns with 6 spf RDX deep penetrating charges >40"	Per Meter	100	
	Using 4 1/2" HSC guns with 5/6 spf RDX deep penetrating charges > 70"	Per Meter	400	
	Using 2 1/8" RDX, 4/6 SPF (Gun)	Per Meter	50	
	Using 1 11/16" RDX, 4/6 SPF (Gun)	Per Meter	50	
	Cement Squeeze Job In Casing Using 4 1/2"/3 3/8" Gun With 5 SPM Using RDX Charges	Per Meter	15	
	Tubing Conveyed Perforation charges	Per run	10	
	Tubing Puncture	Per Job	5	
	Tubing Cutter	Per Job	10	
	Casing cutter	Per Job	10	
	Split Shot Cutter	Per Job	10	
	Colloidal / Severing Services	Per Job	5	
	Back off Services	Per Job	10	
	Pressure Control equipment's of 5K rating (Greece / Oil Injector system, Raiser pipes, Greece / oil, Sinkers bars for weight and hole probing purpose, or any other item required for carrying out job)	Per Job	15	