Sun Petrochemicals Private Limited
Corporate Office: 8th, 9th & 10th Floor, ATL Corporate Park, Saki Vihar Road,
Powai, Mumbai - 400 072, Maharashtra, BHARAT.
CIN: U24219MH1995PTC464242
Tel: +91 22 69325300, + 91 22 28470484
Website: www.sunpetro.com; Email Id: info.sunpetro@sunpetro.com

No. SunPetro/Bhaskar/Crude Oil Pump House/2026-27/SPPL-293/Bulletin-3 **Date: 19.11.2026**

BULLETIN #3

Sub: Construction of Crude Oil Transfer Pump House Along with All Associated Works at Bhaskar-I Field, Gujarat.

Ref: Tender No.: SunPetro/Bhaskar/Crude Oil Pump House/2026-27/SPPL-293

Sun Petrochemicals Private Limited (**SunPetro)**, hereby issues the following amendment to the above-mentioned Tender.

The Required documents have been provided separately as an annexure with this Bulletin.

Sl. No.	Clause No.	In Lieu of	To be read as
1.	New clause	New clause in BOQ, Table-A Civil & Structural as sl. no. 21 (bidder has to quote against this item)	**Item no.** 21 **Description**: Supply/fabrication and installation of porta cabin required for MCC for electrical panels as per technical specifications attached. Job includes supply of all material, architectural / interior works, electrical works, Supply & Installation of MCT Block, ACs and all jobs enumerated in technical specifications. **Quantity:** 800 **Unit :** sq. ft.
2.	New clause	New clause in BOQ, Table-A Civil & Structural as sl. no. 22number (This item is added for clarity and for the purpose of making payment. Bidder need not quote against this item.	**Item no.** 22 **Description**: Construction of foundation for Feeder/ Booster pumps (VS-6) – 3 Nos. (including one for future pump). The construction of foundation for VS-6 pump involves driving of casing pipe approximately (1200 mm dia. and 6000 mm length), dewatering, plugging, RCC foundation block, installation of pump barrel (app. 800 mm dia), concreting of annular portion between casing pipe and pump barrel, maintain desired level and co-ordinates. This job shall be executed as an extra item on actual cost basis due to uncertainty in dewatering and requirement of shoring/ strutting, etc.. Casing pipe 1200 mm shall be free issue item and concrete and reinforcement quantities will be measured and paid in respective civil works. Quantity : 3 Unit: number
3.	New clause	New clause in BOQ, Table-A Civil & Structural as sl. no. 23 (Bidder has to quote against this item	**Item no.** 22 **Description**: Supply, fabrication and installation of GI grating heavy duty as per standard engineering practice for cross overs, pit covers, etc., drawing, size, details shall be worked out during detailed engineering. **Quantity:** 100 **Unit :** Kg
4.		Specifications and Vendor list of Online Water cut Analyser	**Vendor**: Drexelbrook **Local supplier**: SHRIRANG AUTOMATION AND CONTROLS, Sachin, Gujarat 394230 **Model**: Universal V CM Model with temperature correction **Model No.**: VC01040100253E +700-1202-021-BA0-101-727.07-88XXXXX
5.	Clause 13 & 14 of page 37 of 185 & Wherever appearing	Connection with existing 10" export line.	The connection with 10" export line shall be made in overground portion of line. Reference to underground line may be replaced with overground line.
6.	Sl. no. 8 & 9 of page 67 of 185 (Responsibility Matrix) and Table D sl. no. A1 & A2,		The Feeder Booster pumps & Export pumps along with ARC valves and Strainers will be free issue. The bidder shall quote only installation charges against these items.

	Table-E sl. no. 60, 61, 75 & 76		
7.	Sl. no. 8.2.1 Page 141 of 185	..... shall be completed within eighteen (18) months from the date of LOA.....	..... shall be completed within twelve (12) months from the date of LOA.....
8.	Sl. no. 8.25.4 Page 158 of 185	..... Company shall provide boarding and lodging to the Contractor's personnel while at work.	This line is deleted. Contractor shall provide boarding and lodging to their personnel.
9.	Sl. no. 8.33.9 Page 164 of 185	Land for Contractor's office, Godown and workshop "Unless otherwise..... recourse to the Company"	Land for Contractor's office, Godown and workshop SunPetro shall provide open space of 70 x 70 mtr. on as is where is basis, free of cost for site office/ warehouse/ workshop. Contractor shall restore the same after work completion.
10.	New Clause	New clause in Bill of Quantities (BOQ)/ Price Schedule page 80 of 185 as sl. no. 20.	The bidder will prepare BOQ of all items. Payment will be made on installed basis. All surplus/scrap unused items shall be property of Contractor. No separate spare quantities are required in piping, electrical, instrumentation works. Spares if required will be measured and paid as per BOQ. The spares will be required as part of supply only for Recirculation pumps, drain pumps and EOT crane as per listed spares and vendor recommendation for commissioning, which will be part of quoted price.
11.	Table-D Mechanical page 120 of 185	Unit Rate (INR) - Dismantling	Unit Rate (INR) - Supply
12.	Notes: sl. no. 5 & 10 page 134 of 185	Sl. No. 5 & 10.	deleted
13.	New Clause	New clause in Bill of Quantities (BOQ)/ Price Schedule page 80 of 185 as sl. no. 21.	The supply of all items (except booster/Feed pumps, export pumps, specified strainer and ARC valves) are in scope of supply of Contractor. The rate should be inclusive of supply, in case not mentioned separately.
14.	New Clause	New clause in Bill of Quantities (BOQ)/ Price Schedule page 80 of 185 as sl. no. 21.	The supply of all items (except booster/Feed pumps, export pumps, specified strainer and ARC valves) are in scope of supply of Contractor. The rate should be inclusive of supply, in case not mentioned separately.
15.		Data sheet and specifications	The data sheet/ specifications of 15 items are attached for compliance.

All other terms and conditions of the Tender remain unchanged.

Regards,

Sun Petrochemicals Pvt. Ltd.